

TEST REPORT FIRES-FR-245-12-AUNE

Cable bearing system and fireboxes BAKS with cables business
Fabryka Kabli MADEX s. j.



This is an electronic version of a test report which was made as a copy of test report officially issued in a paper form. The electronic version of a test report shall be used only for informative purposes. Any information listed in this test report is the property of the sponsor and shall not be used or published without written permission. Contents of this file may only be modified by the editor i.e. Testing laboratory FIRES s.r.o. Batizovce. Sponsor is allowed to publish this test report in parts only with written permission of the editor.



TEST REPORT

FIRES-FR-245-12-AUNE

Tested property: Function in fire
Test method: STN 92 0205: 2012 (ZP-27/2008, DIN 4102-12: 1998-11)
Date of issue: 14. 12. 2012

Name of the product: Cable bearing system and fireboxes BAKS with cables business
Fabryka Kabli MADEX s. j.

Manufacturer: BAKS Kazimierz Sielski, ul. Jagodne 5, 05 - 480 Karczew,
Poland - producer of construction

Fabryka Kabli MADEX s. j., Stefanówka, ul. Żurawia 96,
05 – 462 Wiązowna, Poland – producer of cables

Sponsor: BAKS Kazimierz Sielski, ul. Jagodne 5, 05-480 Karczew, Poland

Task No.: PR-12-0441
Specimens received: 06. 12. 2012
Date of the test: 13. 12. 2012

Technician responsible for the technical side of this report: Bc. Dávid Šubert

Number of pages: 64
Test reports: 5

Copy No.: 2

Distribution list:

Copy No. 1 FIRES, s. r. o., Osloboditeľov 282, 059 35 Batizovce, Slovak Republic
(electronic version)
Copy No. 2 BAKS Kazimierz Sielski, ul. Jagodne 5, 05 - 480 Karczew, Poland (electronic version)
Copy No. 3 Fabryka Kabli MADEX s. j., Stefanówka, ul. Żurawia 96, 05 – 462 Wiązowna, Poland
(electronic version)
Copy No. 4 BAKS Kazimierz Sielski, ul. Jagodne 5, 05-480 Karczew, Poland
Copy No. 5 Fabryka Kabli MADEX s. j., Stefanówka, ul. Żurawia 96, 05 – 462 Wiązowna, Poland

This report includes accreditation mark SNAS with additional mark ILAC-MRA. SNAS is signatory of ILAC-MRA, Mutual recognition agreement (of accreditation), which is focused on promoting of international acceptance of accredited laboratory data and reducing technical barriers to trade, such as the retesting of products on markets of signatories. More information about ILAC-MRA is on www.ilac.org. Signatories of ILAC-MRA are e.g. SNAS (Slovakia), CAI (Czech Republic), PCA (Poland), DakKS (Germany) or BMWA (Austria). Up to date list of ILAC-MRA signatories is on www.ilac.org/documents/mra_signatories.pdf. FIRES, s.r.o. Batizovce is full member of EGOLF also, more information www.egolf.org.uk.



1. INTRODUCTION

This test report contains the results of test carried out by laboratory of FIRES, s.r.o. in Batizovce, accredited by SNAS for testing. Certificate of accreditation No.: S-159. The purpose of the test was to gain information for product classification.

Test of function in fire was carried out according to standard STN 92 0205: 2012. Similar standards and regulations for tests of function in fire are ZP-27/2008 PAVUS and DIN 4102-12: 1998-11.

Deviations from standard at the test according to ZP-27/2008: This test was carried out according to standard STN 92 0205: 2012 and meets also all requirements of ZP-27/2008 and test results can be directly used for classification of tested cables according to ZP-27/2008. There are no deviations identified in process and carrying out of test.

Deviations from standard at the test according to DIN 4102-12: 1998-11: This test was carried out according to standard STN 92 0205: 2012 and meets requirements of DIN 4102-12: 1998-11. Basic deviation in process and carrying out of test between these standards is in measuring and in control of temperature in the test furnace. According to STN 92 0205: 2012, plate thermometers according to EN 1363-1: 1999 are used. According to DIN 4102-12: 1998-11, common thermocouples of construction which was used for this measurement till issue of EN 1363-1:1999 are used. Measurement by plate thermometers acc. to EN 1363-1: 1999 can be considered as stricter method of temperature control in test furnace in compare with thermocouples used till issue of EN 1363-1: 1999. Therefore, it is possible to use results of test according to STN 92 025: 2012 for classification of tested cables according to DIN 4102-12: 1998-11, but not conversely. Identified deviation results in stricter course of test and it can lead to reduced classification of tested cables what is accepted as enhanced security in practice.

Representatives from the sponsor's side witnessing the test:

Mr. Jacek Kliczek	BAKS Kazimierz Sielski
Mr. Dariusz Gowronski	BAKS Kazimierz Sielski
Mr. Norbert Łuczak	BAKS Kazimierz Sielski
Mr. Artur Twardowski	Fabryka Kabli MADEX s. j.
Mr. Ireneusz Lipiński	Fabryka Kabli MADEX s. j.
Mr. Juraj Antol	STRADER s.r.o.

test directed by	Ing. Marek Gorlický
test carried out by	Bc. Dávid Šubert
operator	Miroslav Hudák

2. MEASURING EQUIPMENT

Identification number	Measuring equipment	Note
F 90 004	Vertical test furnace for fire resistance testing	-
F 69 010	PLC system for data acquisition and control TECOMAT TC 700	-
F 40 017	Control and communication software to PLC TECOMAT TC 700	-
F 40 018	SW Reliance	-
F 40 019	Visual and calculating software to PLC TECOMAT TC 700	-
F 40 020	Driver Tecomat – Reliance (SW)	-
F 69 009	PLC system for data acquisition and climate control TECOMAT TC 604	-
F 60 001 - F 60 009	Sensors of temperature and relative air humidity	climatic conditions measuring
F 71 008, F 71 009	Transducer of differential pressure (-50 to + 150) Pa	pressure inside the test furnace



Identification number	Measuring equipment	Note
F 10 521 - F 10 528	Plate thermometers	temperature inside the test furnace, according to EN 1363-1
F 10 701	Sheathed thermocouple type K Ø 3 mm	ambient temperature
F 54 020	Digital calliper (0 to 200) mm	-
F 54 059	Racking meter	-
F 57 007	Digital stop-watch	-
F 96 015	Test signal panel	-

3. PREPARATION OF THE SPECIMENS

Testing laboratory didn't take off individual components of the specimens. Components take-off and its delivering to the testing laboratory were carried out by the test sponsor. Assembling of the supporting system into the test furnace and mounting of cables and weights into the supporting system was carried out by workers of BAKS Kazimierz Sielski and Fabryka Kabli MADEX s. j. under supervision of laboratory technician.

4. PREPARATION OF THE TEST

4.1 DESCRIPTION OF THE SPECIMENS STRUCTURE

Test specimen comprised from cable bearing system BAKS Kazimierz Sielski company – cable trays, cable ladders, cable clips and fireboxes with accessories (consoles, supports, hangers etc.) and power and communication halogen free cables of Fabryka Kabli MADEX s. j. company.

Cables

Used cables by test:	NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE	(14x)
	NHXH FE180 PH90/E90 0,6/1kV 4x50 RM	(18x)
	NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE	(12x)
	NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM	(8x)
	NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	(10x)
	HTKSH PH90 1x2x1,0	(19x)
	HTKSHekw PH90 1x2x1,0	(16x)

The length of cables was 5,1 m, 3,5 m from that was exposed to fire.

Power and communication halogen free cables were fixed in the trays, ladders and mesh trays by steel clips in the points of allowed bending radius.

Cable bearing systems were made of following constructions:

Suspension tracks No. 1 and 2

Tracks are made of three consoles (WPC/WPCO1000) which were fixed to ceiling by two threaded rods (PG M10) in spacing of 1200 mm. Two brackets (WMC/WMCO400) were fixed to consoles by screws (SM M10x30). Holders (UPW/UPWO) were fixed at the end of brackets with screws (SGN M8x14). Brackets were fixed through these holders by threaded rods (PG M10) with washer and nuts M10 to ceiling holders (USV/USOV).

Tracks No. 1:

Cable trays (KCP/KCOP400H60/3, steel sheet thickness 1,5 mm) fixed together by two junctions (LPP/LPOP H60N) and screws (SGN M8x14) on sides and by junction (BL/BLO400N) and screws (SGN M6x12) on the bottom. Trays were fixed to supports by screws (SGN M6x12) and loaded with 10kg.m^{-1} .

**Track No. 2:**

Cable ladders (DGOP400H60/B400, steel sheet thickness 1,5 mm, spacing of transoms 150 mm) fixed together by two junctions (LDC/LDOCH60N) and screws (SGN M8x14) on sides. Ladders were fixed to supports by junctions (ZM/ZMO) and by screws (SGN M8x14) and loaded with 20kg.m^{-1} .

Suspension tracks No. 3 - 8

Tracks are made of three console combined of two horizontal supports (CWP/CWOP40H40/05) which are fixed to two threaded rods (PGM10) by washers (PP10) and nuts (NSM10). Threaded rods were fixed to ceiling in spacing of 1500 mm.

Track No. 3:

Cable mesh trays (KDS/KDSO400H60/3, steel wire $\varnothing$ 4,5 mm) fixed together by junctions (USS/USSO). Mesh trays were fixed to supports by junctions (ZS/ZSO) and loaded with 20kg.m^{-1} . Cables were fixed to ledges by cable clips (UKZ/UKZO1).

Track No. 4:

Cable mesh trays (KDS/KDSO400H60/3, steel wire $\varnothing$ 4,5 mm) fixed together by junctions (USS/USSO). Mesh trays were fixed to supports by junctions (ZS/ZSO) and loaded with 20kg.m^{-1} . Cables were fixed to ledges by cable clips (UKZ/UKZO1).

Tracks No. 5:

Cable trays (KGJ/KGOJ400H60/3, steel sheet thickness 0,9 mm) fixed together by screws (SGN M6x12). Trays were fixed to supports by screws (SGN M6x12) and loaded with 20kg.m^{-1} .

Tracks No. 6:

Cable trays (KGL/KGOL300H60/3, steel sheet thickness 0,7 mm) fixed together by screws (SGN M6x12). Trays were fixed to supports by screws (SGN M6x12) and loaded with 20kg.m^{-1} .

Tracks No. 7:

Cable trays (KGL/KGOJ400H60/3, steel sheet thickness 0,9 mm) fixed together by screws (SGN M6x12). Trays were fixed to supports by screws (SGN M6x12) and loaded with 20kg.m^{-1} .

Tracks No. 8:

Cable trays (KGL/KGOL300H60/3, steel sheet thickness 0,7 mm) fixed together by screws (SGN M6x12). Trays were fixed to supports by screws (SGN M6x12) and loaded with 20kg.m^{-1} .

Track No. 9

Supporting construction was made of gypsum boards 12 mm thick fixed to side wall of furnace. Track was made of cable clips (UDF) which were fixed to gypsum boards by dowels (MOLLY 5x52/58) in spacing of 600 mm.

Track No. 10

Track was made of two fireboxes (BAKS PMO1) and two fireboxes (BAKS PMO2) fixed to ceiling. Cables which were connected to firebox were fixed to ceiling by cable clips KSA in spacing of 600 mm.

Suspension track No. 11

Cable mesh trays (KDSO60H60/B60, steel wire $\varnothing$ 4,5 mm) fixed together by junctions (USSO). Trays were fixed to ceiling by holders (WKS/WKSO60) and threaded rods (PG M6) and loaded with $1,5\text{kg.m}^{-1}$.

Track No. 12

Ceiling ledges (SDOP 700) were fixed to ceiling by threaded rods (PG M6) in spacing of 600 mm. Cables were fixed to ledges by cable clips (UK/UKO1).

Track No. 13

Track was made of ceiling clips (KSA) which were fixed to ceiling by in spacing of 600 mm.

Track No. 14

Track was made of cable holders (UDF) which were fixed to side wall of furnace by dowels (KMHM – 4x60) in spacing of 600 mm.



All bearing systems were from steel, galvanized according to the Sendzimir method PN-EN 10327:2005.

More detailed information about construction of specimens is shown in the drawings which form an integral part of this test report. Drawings were delivered by sponsor.

All the information about technical specifications of used materials and semi-products, information about their type sign were delivered by sponsor. This information was not subject of the inspection of specimens. Parameters which were checked are quoted in paragraph 4.3.

4.2 DESCRIPTION OF SPECIMENS FIXATION

The test specimens were fixed on the ceiling of the test furnace which was created from aerated concrete panels with dimensions (4000 x 600 x 240) mm – 6 pieces and fixed to side walls made of aerated concrete blocks YTONG, 250 mm thick. Ceiling panels were jointed by beam which provides balance deflection of the ceiling.

The type of specimen's fixation into the test furnace is shown in drawing documentation and it was selected by the sponsor.

4.3 INSPECTION OF SPECIMENS

Before and after the function in fire test, conformity of drawings and test specimens was checked. Specimens corresponded to the drawings which are part of this test report. Inspection of specimens consisted of visual review of the test specimens, used materials as well as size verification (number and cross sections of conductors, thickness, measurements of cables and trays) and also the way of specimens fixation to supporting construction was subject of inspection.

4.4 CLIMATIC CONDITIONING OF SPECIMENS

Test specimens were stored in the hall of testing laboratory under the following climatic conditions:

Ambient air temperature [°C]

mean	19,6
standard deviation	1,6

Relative air humidity [%]

mean	45,9
standard deviation	2,6

The humidity equilibrium state of test specimens was not determined. Test specimens did not comprise hygroscopic materials.

5. CARRYING OUT OF THE TEST

5.1 TEST GENERALLY

The test was carried out in horizontal test furnace with dimensions of (3500 x 3000 x 2750) mm (length x width x height).

5.2 CONDITIONS OF THE TEST

Conditions in the test furnace (temperature – standard temperature/time curve, pressure, content of O₂) as well as in the testing room (ambient temperature) corresponded to EN 1363-1 during the test. Detailed information is part of this test report, or in Quality records of the testing laboratory.

Values characterizing environment in the testing room directly before the test:

Date of the test	Relative air humidity [%]	Ambient air temperature [°C]
13. 12. 2012	44,3	18,3



5.3 RESULTS OF THE TEST

Measured values are stated in this test report.

6. CLOSING

Evaluation of the test:

Specimen No.	Cables	Track No.	Time to first failure / interruption of conductor
1	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM	14	90 minutes no failure / interruption
2	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
3	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
4	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
5	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE	8	90 minutes no failure / interruption
6	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
7	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		71 minutes
8	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
9	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE	7	90 minutes no failure / interruption
10	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
11	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
12	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
13	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM	13	90 minutes no failure / interruption
14	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
15	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE	6	90 minutes no failure / interruption
16	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
17	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		90 minutes no failure / interruption
18	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		90 minutes no failure / interruption
19	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE	5	90 minutes no failure / interruption
20	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
21	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		90 minutes no failure / interruption
22	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		87 minutes
23	2 cables NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	12	90 minutes no failure / interruption
24	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		81 minutes
25	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE	11	90 minutes no failure / interruption
26	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
27	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE	4	90 minutes no failure / interruption
28	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
29	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		90 minutes no failure / interruption
30	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM		90 minutes no failure / interruption
31	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	3	90 minutes no failure / interruption
32	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		90 minutes no failure / interruption
33	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
34	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
35	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
36	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
37	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE + fireboxes PMO2	10	90 minutes no failure / interruption
38	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE + fireboxes PMO2		90 minutes no failure / interruption



Specimen No.	Cables	Track No.	Time to first failure / interruption of conductor
39	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	2	90 minutes no failure / interruption
40	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		90 minutes no failure / interruption
41	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
42	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
43	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	1	90 minutes no failure / interruption
44	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		90 minutes no failure / interruption
45	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
46	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM		90 minutes no failure / interruption
47	2 cables NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	9	42 minutes
48	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		90 minutes no failure / interruption
49	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		90 minutes no failure / interruption
52	2 cables HTKSHekw PH90 1x2x1,0	14	90 minutes no failure / interruption
53	2 cables HTKSH PH 90 1x2x1,0		90 minutes no failure / interruption
54	2 cables HTKSH PH 90 1x2x1,0	8	26 minutes
55	2 cables HTKSH PH 90 1x2x1,0	7	36 minutes
56	2 cables HTKSHekw PH90 1x2x1,0	6	23 minutes
57	2 cables HTKSHekw PH90 1x2x1,0	5	34 minutes
58	2 cables HTKSH PH 90 1x2x1,0	12	90 minutes no failure / interruption
59	2 cables HTKSH PH 90 1x2x1,0	11	79 minutes
60	2 cables HTKSHekw PH90 1x2x1,0		47 minutes
61	2 cables HTKSHekw PH90 1x2x1,0	4	28 minutes
62	2 cables HTKSH PH 90 1x2x1,0	3	30 minutes
63	cable HTKSH PH 90 1x2x1,0 + fireboxes PMO1	10	90 minutes no failure / interruption
64	2 cables HTKSHekw PH90 1x2x1,0	2	31 minutes
65	2 cables HTKSH PH 90 1x2x1,0		28 minutes
66	2 cables HTKSHekw PH90 1x2x1,0	1	35 minutes
67	2 cables HTKSH PH 90 1x2x1,0		39 minutes
68	2 cables HTKSHekw PH90 1x2x1,0	9	90 minutes no failure / interruption
69	2 cables HTKSH PH 90 1x2x1,0		90 minutes no failure / interruption

The fire test was discontinued in 94th minute at the request of test sponsor.

Specimens S1 – S49 were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
Specimens S52 – S69 were tested by one-phase voltage supply 1 x 110V with LED diodes 3V /0,03W.
Circuit breakers with rating 3 A were used.



Measured values inside the test furnace

Time t [min]	Temperature [°C]											Deviation d _e [%]	Pressure p [Pa]
	Td1	Td2	Td3	Td4	Td5	Td6	Td7	Td8	Tave	Tn	To		
0	11,1	10,6	10,8	11,4	13,4	13,4	13,2	14,0	12,2	20,0	18,3	0,0	17,8
5	552,5	594,5	652,7	554,8	548,1	645,1	645,0	568,8	595,2	576,0	18,4	-1,0	17,7
10	628,1	675,0	701,6	697,1	631,1	678,3	687,7	691,0	673,7	678,0	18,4	-0,1	18,3
15	690,4	714,0	758,5	761,7	731,2	755,9	789,2	767,7	746,1	739,0	18,5	0,2	17,7
20	734,5	754,2	800,6	794,6	780,1	805,2	833,9	821,1	790,5	781,0	18,5	0,4	18,2
25	761,3	802,7	862,8	871,4	792,0	819,0	864,8	893,5	833,4	815,0	18,6	0,7	17,8
30	826,0	848,0	876,3	844,2	814,5	831,7	849,0	848,2	842,2	842,0	18,6	0,7	17,7
35	834,5	852,2	869,7	846,2	857,4	856,1	859,5	849,5	853,1	865,0	18,7	0,3	17,6
40	859,5	864,6	875,6	849,3	875,4	863,8	878,2	854,2	865,1	885,0	18,7	0,0	17,6
45	863,9	883,8	906,1	900,2	873,4	882,8	904,8	903,6	889,8	902,0	18,8	-0,2	17,7
50	877,0	898,8	921,1	917,3	888,0	898,8	920,2	923,4	905,6	918,0	18,8	-0,3	18,3
55	898,4	921,2	939,6	943,1	909,0	919,9	942,0	946,0	927,4	932,0	18,9	-0,4	18,3
60	918,3	939,3	960,7	962,3	928,8	939,3	964,3	968,0	947,6	945,0	19,0	-0,4	18,2
65	936,5	954,9	977,5	978,3	944,2	955,5	980,0	986,7	964,2	957,0	19,0	-0,3	18,3
70	950,4	968,4	987,1	989,5	958,6	967,6	988,4	993,4	975,4	968,0	19,0	-0,2	17,7
75	961,3	977,2	995,7	998,9	969,6	978,6	997,3	1002,8	985,2	979,0	19,1	-0,1	17,6
80	972,4	988,9	1004,5	1006,4	980,8	986,9	1008,2	1010,0	994,8	988,0	19,1	0,0	17,9
85	981,0	994,5	1010,9	1011,8	1000,3	994,5	1014,3	1017,9	1003,2	997,0	19,2	0,0	17,8
90	988,8	1002,3	1018,0	1016,2	996,4	1002,3	1019,9	1021,6	1008,2	1006,0	19,3	0,0	17,6
91	990,4	1003,1	1019,4	1019,5	997,4	1002,0	1021,5	1024,4	1009,7	1008,0	19,3	0,0	18,2
92	991,2	1005,0	1020,0	1019,8	998,7	1002,8	1022,2	1023,8	1010,4	1009,0	19,2	0,0	18,0
93	994,9	1007,2	1022,8	1022,7	1001,6	1005,7	1024,2	1026,7	1013,2	1011,0	19,3	0,0	17,6

Tave Average temperature in the test furnace calculated from plate thermometers


Tn Standard temperature in the test furnace laid down to test guideline

To Ambient temperature

d_e Deviation of the average temperature from the standard temperature calculated according to test guideline




p Pressure inside the test furnace measured under the ceiling of the test furnace

Layout of measuring points inside the test furnace:





Measured values inside the test furnace /graph




Measured time of tested specimens from S1 to S10 - power cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S1	1-L1	no failure / interruption
	2-L2	no failure / interruption
	3-L3	no failure / interruption
	4-PEN	no failure / interruption
S2	5-L1	no failure / interruption
	6-L2	no failure / interruption
	7-L3	no failure / interruption
	8-PEN	no failure / interruption
S3	9-L1	no failure / interruption
	10-L2	no failure / interruption
	11-L3	no failure / interruption
	12-PEN	no failure / interruption
S4	13-L1	no failure / interruption
	14-L2	no failure / interruption
	15-L3	no failure / interruption
	16-PEN	no failure / interruption
S5	17-L1	no failure / interruption
	18-L2	no failure / interruption
	19-L3	no failure / interruption
	20-PEN	no failure / interruption
S6	21-L1	no failure / interruption
	22-L2	no failure / interruption
	23-L3	no failure / interruption
	24-PEN	no failure / interruption
S7	25-L1	71:30
	26-L2	x
	27-L3	x
	28-PEN	x
S8	29-L1	no failure / interruption
	30-L2	no failure / interruption
	31-L3	no failure / interruption
	32-PEN	no failure / interruption
S9	33-L1	no failure / interruption
	34-L2	no failure / interruption
	35-L3	no failure / interruption
	36-PEN	no failure / interruption
S10	37-L1	no failure / interruption
	38-L2	no failure / interruption
	39-L3	no failure / interruption
	40-PEN	no failure / interruption

Specimen No.	Cables
1	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
2	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
3	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
4	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
5	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
6	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
7	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
8	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
9	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
10	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE

- x Conductor was turned off manually after permanent interruption / failure of other conductors in the cable
 Power cables were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
 Circuit breakers with rating 3 A were used.


Measured time of tested specimens from S11 to S20 - power cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S11	41-L1	no failure / interruption
	42-L2	no failure / interruption
	43-L3	no failure / interruption
	44-PEN	no failure / interruption
S12	45-L1	no failure / interruption
	46-L2	no failure / interruption
	47-L3	no failure / interruption
	48-PEN	no failure / interruption
S13	49-L1	no failure / interruption
	50-L2	no failure / interruption
	51-L3	no failure / interruption
	52-PEN	no failure / interruption
S14	53-L1	no failure / interruption
	54-L2	no failure / interruption
	55-L3	no failure / interruption
	56-PEN	no failure / interruption
S15	57-L1	no failure / interruption
	58-L2	no failure / interruption
	59-L3	no failure / interruption
	60-PEN	no failure / interruption
S16	61-L1	no failure / interruption
	62-L2	no failure / interruption
	63-L3	no failure / interruption
	64-PEN	no failure / interruption
S17	65-L1	no failure / interruption
	66-L2	no failure / interruption
	67-L3	no failure / interruption
	68-PEN	no failure / interruption
S18	69-L1	no failure / interruption
	70-L2	no failure / interruption
	71-L3	no failure / interruption
	72-PEN	no failure / interruption
S19	73-L1	no failure / interruption
	74-L2	no failure / interruption
	75-L3	no failure / interruption
	76-PEN	no failure / interruption
S20	77-L1	no failure / interruption
	78-L2	no failure / interruption
	79-L3	no failure / interruption
	80-PEN	no failure / interruption

Specimen No.	Cables
11	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
12	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
13	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
14	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
15	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
16	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
17	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
18	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
19	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
20	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE

Power cables were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
Circuit breakers with rating 3 A were used.


Measured time of tested specimens from S21 to S30 - power cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S21	81-L1	no failure / interruption
	82-L2	no failure / interruption
	83-L3	no failure / interruption
	84-PEN	no failure / interruption
S22	85-L1	x
	86-L2	x
	87-L3	87:21
	88-PEN	x
S23	89-L1	no failure / interruption
	90-L2	no failure / interruption
	91-L3	no failure / interruption
	92-PEN	no failure / interruption
S24	93-L1	x
	94-L2	81:02
	95-L3	x
	96-PEN	x
S25	97-L1	no failure / interruption
	98-L2	no failure / interruption
	99-L3	no failure / interruption
	100-PEN	no failure / interruption
S26	101-L1	no failure / interruption
	102-L2	no failure / interruption
	103-L3	no failure / interruption
	104-PEN	no failure / interruption
S27	105-L1	no failure / interruption
	106-L2	no failure / interruption
	107-L3	no failure / interruption
	108-PEN	no failure / interruption
S28	109-L1	no failure / interruption
	110-L2	no failure / interruption
	111-L3	no failure / interruption
	112-PEN	no failure / interruption
S29	113-L1	no failure / interruption
	114-L2	no failure / interruption
	115-L3	no failure / interruption
	116-PEN	no failure / interruption
S30	117-L1	no failure / interruption
	118-L2	no failure / interruption
	119-L3	no failure / interruption
	120-PEN	no failure / interruption

Specimen No.	Cables
21	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
22	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
23	2 cables NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
24	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
25	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
26	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
27	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
28	cable NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
29	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM
30	cable NHXCH FE180 PH90/E90 0,6/1kV 4x50/25 RM

- x Conductor was turned off manually after permanent interruption / failure of other conductors in the cable
 Power cables were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
 Circuit breakers with rating 3 A were used.


Measured time of tested specimens from S31 to S40 - power cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S31	121-L1	no failure / interruption
	122-L2	no failure / interruption
	123-L3	no failure / interruption
	124-PEN	no failure / interruption
S32	125-L1	no failure / interruption
	126-L2	no failure / interruption
	127-L3	no failure / interruption
	128-PEN	no failure / interruption
S33	129-L1	no failure / interruption
	130-L2	no failure / interruption
	131-L3	no failure / interruption
	132-PEN	no failure / interruption
S34	133-L1	no failure / interruption
	134-L2	no failure / interruption
	135-L3	no failure / interruption
	136-PEN	no failure / interruption
S35	137-L1	no failure / interruption
	138-L2	no failure / interruption
	139-L3	no failure / interruption
	140-PEN	no failure / interruption
S36	141-L1	no failure / interruption
	142-L2	no failure / interruption
	143-L3	no failure / interruption
	144-PEN	no failure / interruption
S37	145-L1	no failure / interruption
	146-L2	no failure / interruption
	147-L3	no failure / interruption
	148-PEN	no failure / interruption
S38	149-L1	no failure / interruption
	150-L2	no failure / interruption
	151-L3	no failure / interruption
	152-PEN	no failure / interruption
S39	153-L1	no failure / interruption
	154-L2	no failure / interruption
	155-L3	no failure / interruption
	156-PEN	no failure / interruption
S40	157-L1	no failure / interruption
	158-L2	no failure / interruption
	159-L3	no failure / interruption
	160-PEN	no failure / interruption

Specimen No.	Cables
31	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
32	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
33	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
34	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE
35	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
36	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
37	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE + fireboxes PMO2
38	cable NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE + fireboxes PMO2
39	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
40	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE

Power cables were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
Circuit breakers with rating 3 A were used.


Measured time of tested specimens from S41 to S49 - power cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S41	161-L1	no failure / interruption
	162-L2	no failure / interruption
	163-L3	no failure / interruption
	164-PEN	no failure / interruption
S42	165-L1	no failure / interruption
	166-L2	no failure / interruption
	167-L3	no failure / interruption
	168-PEN	no failure / interruption
S43	169-L1	no failure / interruption
	170-L2	no failure / interruption
	171-L3	no failure / interruption
	172-PEN	no failure / interruption
S44	173-L1	no failure / interruption
	174-L2	no failure / interruption
	175-L3	no failure / interruption
	176-PEN	no failure / interruption
S45	177-L1	no failure / interruption
	178-L2	no failure / interruption
	179-L3	no failure / interruption
	180-PEN	no failure / interruption
S46	181-L1	no failure / interruption
	182-L2	no failure / interruption
	183-L3	no failure / interruption
	184-PEN	no failure / interruption
S47	185-L1	42:26
	186-L2	42:26
	187-L3	x
	188-PEN	x
S48	189-L1	no failure / interruption
	190-L2	no failure / interruption
	191-L3	no failure / interruption
	192-PEN	no failure / interruption
S49	193-L1	no failure / interruption
	194-L2	no failure / interruption
	195-L3	no failure / interruption
	196-PEN	no failure / interruption

Specimen No.	Cables
41	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
42	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
43	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
44	cable NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
45	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
46	cable NHXH FE180 PH90/E90 0,6/1kV 4x50 RM
47	2 cables NHXH-J FE180 PH90/E90 0,6/1kV 5x16 RE
48	2 cables NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE
49	2 cables NHXH FE180 PH90/E90 0,6/1kV 4x1,5 RE

- x Conductor was turned off manually after permanent interruption / failure of other conductors in the cable
 Power cables were tested by three-phase voltage supply 3 x 230/400V with bulbs 240V / 60 W.
 Circuit breakers with rating 3 A were used.


Measured time of tested specimen S52 to S61 - communication cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S52A	209-L	no failure / interruption
	210-PEN	no failure / interruption
S52B	211-L	no failure / interruption
	212-PEN	no failure / interruption
S53A	213-L	no failure / interruption
	214-PEN	no failure / interruption
S53B	215-L	no failure / interruption
	216-PEN	no failure / interruption
S54A	217-L	30:23
	218-PEN	x
S54B	219-L	26:16
	220-PEN	x
S55A	221-L	37:48
	222-PEN	x
S55B	223-L	36:59
	224-PEN	x
S56A	225-L	24:41
	226-PEN	x
S56B	227-L	23:29
	228-PEN	x
S57A	229-L	34:04
	230-PEN	x
S57B	231-L	34:53
	232-PEN	x
S58A	233-L	no failure / interruption
	234-PEN	no failure / interruption
S58B	235-L	no failure / interruption
	236-PEN	no failure / interruption
S59A	237-L	no failure / interruption
	238-PEN	no failure / interruption
S59B	239-L	79:27
	240-PEN	x
S60A	241-L	47:58
	242-PEN	x
S60B	243-L	no failure / interruption
	244-PEN	no failure / interruption
S61A	245-L	29:59
	246-PEN	x
S61B	247-L	28:11
	248-PEN	x

Specimen No.	Cables
52	2 cables HTKSHekw PH90 1x2x1,0
53	2 cables HTKSH PH 90 1x2x1,0
54	2 cables HTKSH PH 90 1x2x1,0
55	2 cables HTKSH PH 90 1x2x1,0
56	2 cables HTKSHekw PH90 1x2x1,0
57	2 cables HTKSHekw PH90 1x2x1,0
58	2 cables HTKSH PH 90 1x2x1,0
59	2 cables HTKSH PH 90 1x2x1,0
60	2 cables HTKSHekw PH90 1x2x1,0
61	2 cables HTKSHekw PH90 1x2x1,0

- x Conductor was turned off manually after permanent interruption / failure of other conductors in the cable
 Signal cables were tested by three-phase voltage supply 1 x 110V with LED diodes 3V / 0,03W.
 Circuit breakers with rating 3 A were used.


Measured time of tested specimens from S62 to S67 - communication cables

Specimen	Bulbs	Time to permanent failure / interruption [min:s]
S62A	249-L	30:18
	250-PEN	x
S62B	251-L	38:12
	252-PEN	x
S63A	253-L	no failure / interruption
	254-PEN	no failure / interruption
S63B	255-L	no failure / interruption
	256-PEN	no failure / interruption
S64A	257-L	34:22
	258-PEN	x
S64B	259-L	31:21
	260-PEN	x
S65A	261-L	28:56
	262-PEN	x
S65B	263-L	28:25
	264-PEN	x
S66A	265-L	35:26
	266-PEN	x
S66B	267-L	35:40
	268-PEN	x
S67A	269-L	39:44
	270-PEN	x
S67B	271-L	65:14
	272-PEN	x
S68A	273-L	no failure / interruption
	274-PEN	no failure / interruption
S68B	275-L	no failure / interruption
	276-PEN	no failure / interruption
S69A	273-L	no failure / interruption
	274-PEN	no failure / interruption
S69B	275-L	no failure / interruption
	276-PEN	no failure / interruption

Specimen No.	Cables
62	2 cables HTKSH PH 90 1x2x1,0
63	cable HTKSH PH 90 1x2x1,0 + fireboxes PMO1
64	2 cables HTKSHekw PH90 1x2x1,0
65	2 cables HTKSH PH 90 1x2x1,0
66	2 cables HTKSHekw PH90 1x2x1,0
67	2 cables HTKSH PH 90 1x2x1,0

- x Conductor was turned off manually after permanent interruption / failure of other conductors in the cable
Signal cables were tested by three-phase voltage supply 1 x 110V with LED diodes 3V / 0,03W.
Circuit breakers with rating 3 A were used.



PHOTOS



Photo taken before the test.



Photo taken before the test.



Photo taken before the test.



PHOTOS



Photo taken before the test.



Photo taken before the test.



Photo taken before the test.



PHOTOS



Photo taken during the test.



Photo taken during the test.



Photo taken during the test.



PHOTOS



Photo taken after the test.



Photo taken after the test.




Photo taken after the test.



PHOTOS



Photo taken after the test.



Photo taken after the test.



Photo taken after the test.

TECHNICAL DESCRIPTION OF FIRE RESISTANT INSTALLATION CABLES HTKSH PH90; HTKSHekw PH90

1. Technical parameters:

Conductor loop resistance	$\leq 48 \Omega/\text{km}$
Insulation resistance	$\geq 500 \text{ M}\Omega \times \text{km}$
Working capacity of HTKSH cables	$\leq 120 \text{ nF/km}$
Working capacity of HTKSHekw cables	$\leq 200 \text{ nF/km}$
Test voltage (50Hz, 1min.); RMS value conductor/conductor and conductor/shield	1,5KV a.c. or 2,25kV d.c.
Temperature range: - during installation - operating	-5°C do +50°C -30°C do +70°C
Voltage rating, Vrms	300V
Minimum bending radius	10 x outer diameter of the cable
Flame retardance	PN-EN 60332-1-2, IEC 60332-1
Resistance to fire	PH 90 PN-EN 50200
Corrosivity of gases issued during fire	PN-EN 50267-2-3 $\text{pH} \geq 4,3$; conductivity $\leq 10 \mu\text{Smm}^{-1}$
Smoke density	PN-EN 50268-2 transmittance not less than 70%


2. Construction:

- conductor: solid, soft and annealed copper wire according to PN-EN 60228,
- flame barrier: mica tape
- insulation: cross-linked low smoke halogen free polymer type HM2
- twisting: two insulated conductors stranded together
- cable' core: pairs stranded in layers and wrapped with polyester tape; number of pairs in cable
1 - 10
- screen of cable core: Al/PET tape with CuSn drain wire
- sheath: low smoke halogen free flame retardant polymer type HM2; color – red

- Application: For installation in dry and wet rooms, also for direct bedding in concrete, but not for direct burial in ground and not for use in water. The cable has improved flame retardant and may be used in public buildings with high safety requirements and is suitable for control voltages and data transfer in alarm and fire alarm systems.

4. Drawing of cable test specimens

a) HTKSH PH90 1x2x1,0






CABLES

**FABRYKA KABLI
MADER**
Legend:

- 1 – solid copper conductor, diameter 0,98mm
- 2 – mica tape, diameter over tape 1,5mm
- 3 – insulation: low smoke halogen free flame retardant polymer, diameter 2,30mm
- 4 – sheath: low smoke halogen free flame retardant polymer, diameter 6,30mm

b) HTKSHekw PH90 1x2x1,0Legend:

- 1 – solid copper conductor, diameter 0,98mm
- 2 – mica tape, diameter over tape 1,5mm
- 3 – insulation: low smoke halogen free flame retardant polymer, diameter 2,30mm
- 4 – polyester tape, diameter 3,90mm
- 5 – Al/PET tape, diameter over tape 3,95mm
- 6 – sheath: low smoke halogen free flame retardant polymer, diameter 6,60mm

5. Materials characteristic

4.1. Conductor – soft copper wires with following properties:

- elongation at break A_{100} 15÷20%
- tensile strength R_m min. 200 MPa

4.2. Mica tape

- thickness 0,125±0,015mm
- tensile strength min. 100 N/cm
- dielectric constant 1,2
- dielectric strength > 1,2 kV/layer

4.3. Insulation - cross-linked low smoke halogen free polymer

- tensile strength 14 N/mm²
- elongation at break 180%
- hardness 58°Sh D
- oxygen index 36%

4.4. Al/PET tape 9/12 (thickness of aluminum 9μ; thickness of polyester 12μ)

- tensile strength - 36N/15mm
- elongation at break - 11

4.5. Sheath:

- tensile strength 11 MPa
- elongation at break 150%
- hardness 58°Sh D
- oxygen index 45%

TECHNICAL DESCRIPTION OF FIRE RESISTANT CABLE NHXH FE180 PH90/E90 0,6/1 kV

1. Technical parameters:

Nominal voltage U_0/U	0,6/1 kV
Conductor resistance – maximal value at temp. 20°C	according to PN-EN 60228
Test voltage	4 kV, 50 Hz
Insulation resistance - minimal value	$10^{11} \Omega \cdot \text{cm}$
Temperature range: - during installation - operating	-5°C do +50°C -25°C do +90°C
Maximum temperature for short circuit conditions	+ 250°C
Minimum bending radius: - one core cables - multi core cables	15 x outer diameter of the cable 12 x outer diameter of the cable
Flame retardance	PN-EN 60332-1-2, IEC 60332-1, PN-EN 60332-3-24, IEC 60332-3-24
Fire resistance of electric cable systems required to maintain circuit integrity	E90 DIN 4102-12
Circuit integrity	PN-IEC 60331-21 180min (FE180) temp. 750°C
Resistance to fire	PH 90 PN-EN 50200; PN-EN 50362
Corrosivity of gases issued during fire	PN-EN 50267-2-3 $\text{pH} \geq 4,3$; conductivity $\leq 10 \mu\text{Smm}^{-1}$
Smoke density	PN-EN 50268-2 transmittance not less than 70%

2. Construction:

a) conductor: copper according to PN-EN 60228,

RE - round solid class 1

RM – multiwire (stranded) class 2

b) flame barrier: mica tape

c) insulation: cross-linked low smoke halogen free polymer type HX11


d) Core identification: according to PN-HD 308; (J) means yellow – green protective conductor

e) filling sheath: extruded halogen free flame retardant compound

f) sheath: low smoke halogen free flame retardant polymer type HM4; color – orange

3. Application: For installation in dry and wet rooms, also for direct bedding in concrete, but not for direct burial in ground and not for use in water. The cable has improved flame retardant and may be used in public buildings with high safety requirements and is suitable for installation in fire alarm systems, safety lightning and other emergency electrical supply systems.

4. Drawing of cable test specimens



Legend:**a) NHXH FE180 PH90/E90 0,6/1kV 4x1,5RE**

- 1 – solid copper conductor, diameter 1,37mm
- 2 – mica tapes (3 tapes thickness 0,125mm + 1 tape thickness 0,10mm with overlapping 20%), diameter over tapes - 2,4mm
- 3 – insulation: cross-linked low smoke halogen free polymer, diameter 4,58mm
- 4 – filling sheath: low smoke halogen free flame retardant polymer, diameter 13,20mm
- 5 – filler element: low smoke halogen free flame retardant polymer, diameter 1,82mm
- 6 – sheath: low smoke halogen free flame retardant polymer, diameter 16,10mm

b) NHXH FE180 PH90/E90 0,6/1kV 4x50RM

- 1 – multiwire (stranded) class 2 copper conductor, diameter 8,18mm
- 2 – mica tapes (3 tapes thickness 0,125mm + 1 tape thickness 0,10mm with overlapping 20%), diameter over tapes – 9,3mm
- 3 – insulation: cross-linked low smoke halogen free polymer, diameter 11,77mm
- 4 – filling sheath: low smoke halogen free flame retardant polymer, diameter 29,8mm
- 5 – filler element: low smoke halogen free flame retardant polymer, diameter 4,78mm
- 6 – sheath: low smoke halogen free flame retardant polymer, diameter 33,70mm

5. Materials characteristic**4.1. Conductor – soft copper wires with following properties:**

- elongation at break A_{100} - 15÷20%
- tensile strength R_m - min. 200 MPa

4.2. Mica tape

- | | | |
|-----------------------|----------------|---------------|
| - thickness | 0,125±0,015mm | 0,10±0,015 |
| - tensile strength | min. 100 N/cm | min. 100 N/cm |
| - dielectric constant | 1,2 | 1,2 |
| - dielectric strength | > 1,2 kV/layer | > 1 kV/layer |

4.3. Insulation - cross-linked low smoke halogen free polymer

- tensile strength - 11,5 N/mm²
- elongation at break - 280%
- hardness - 45°Sh D
- oxygen index - 33%

4.4. Filling sheath - halogen free compound with low emission of toxic and corrosives gases**4.5. Sheath:**

- tensile strength - 12 MPa
- elongation at break - 180%
- hardness - 50°Sh D
- oxygen index - 40%

TECHNICAL DESCRIPTION OF FIRE RESISTANT CABLE NHXCH FE180 PH90/E90 0,6/1 kV

1. Technical parameters:

Nominal voltage U_0/U	0,6/1 kV
Conductor resistance – maximal value at temp. 20°C	according to PN-EN 60228
Test voltage	4 kV, 50 Hz
Insulation resistance - minimal value	$10^{11} \Omega \cdot \text{cm}$
Temperature range:	- during installation - operating
	-5°C do +50°C -25°C do +90°C
Maximum temperature for short circuit conditions	+ 250°C
Minimum bending radius:	- one core cables - multi core cables
	15 x outer diameter of the cable 12 x outer diameter of the cable
Flame retardance	PN-EN 60332-1-2, IEC 60332-1, PN-EN 60332-3-24, IEC 60332-3-24
Fire resistance of electric cable systems required to maintain circuit integrity	E90 DIN 4102-12
Circuit integrity	PN-IEC 60331-21 180min (FE180) temp. 750°C
Resistance to fire	PH 90 PN-EN 50200; PN-EN 50362
Corrosivity of gases issued during fire	PN-EN 50267-2-3 $\text{pH} \geq 4,3$; conductivity $\leq 10 \mu\text{Smm}^{-1}$
Smoke density	PN-EN 50268-2 transmittance not less than 70%

2. Construction:

a) conductor: copper according to PN-EN 60228,

RE - round solid class 1

RM – multiwire (stranded) class 2

b) flame barrier: mica tape

c) insulation: cross-linked low smoke halogen free polymer type HX11

d) core identification: according to PN-HD 308; (J) means yellow – green protective conductor


e) filling sheath: extruded low smoke halogen free flame retardant compound

f) concentric conductor: helically applied Cu-wires + counter helix

g) sheath: low smoke halogen free flame retardant polymer type HM4; color – orange

3. Application: For installation in dry and wet rooms, also for direct bedding in concrete, but not for direct burial in ground and not for use in water. The cable has improved flame retardant and may be used in public buildings with high safety requirements and is suitable for installation in fire alarm systems, safety lightning and other emergency electrical supply systems.

4. Drawing of cable test specimens



(ed. 30.04.2012)

1

Legend:**a) NHXCH FE180 PH90/E90 0,6/1kV 4x1,5RE**

- 1 – solid copper conductor, diameter 1,37mm
- 2 – mica tapes (3 tapes thickness 0,125mm + 1 tape thickness 0,10mm with overlapping 20%), diameter over tapes - 2,4mm
- 3 – insulation: cross-linked low smoke halogen free polymer, diameter 4,51mm
- 4 – filling sheath: low smoke halogen free flame retardant polymer, diameter 13,20mm
- 5 – filler element: low smoke halogen free flame retardant polymer, diameter 1,74mm
- 6 – concentric conductor, diameter 13,60mm
- 7 – sheath: low smoke halogen free flame retardant polymer, diameter 17,35mm

b) NHXCH FE180 PH90/E90 0,6/1kV 4x50RM

- 1 – multiwire (stranded) class 2 copper conductor, diameter 8,14mm
- 2 – mica tapes (3 tapes thickness 0,125mm + 1 tape thickness 0,10mm with overlapping 20%), diameter over tapes – 9,3mm
- 3 – insulation: cross-linked low smoke halogen free polymer, diameter 11,71mm
- 4 – filling sheath: low smoke halogen free flame retardant polymer, diameter 30,35mm
- 5 – filler element: low smoke halogen free flame retardant polymer, diameter 4,80mm
- 6 – concentric conductor, diameter 31,5mm
- 7 – sheath: low smoke halogen free flame retardant polymer, diameter 36,80mm

5. Materials characteristic**4.1. Conductor – soft copper wires with following properties:**

- elongation at break A_{100} 15÷20%
- tensile strength R_m min. 200 MPa

4.2. Mica tape

- | | | |
|-----------------------|----------------|---------------|
| - thickness | 0,125±0,015mm | 0,10±0,015 |
| - tensile strength | min. 100 N/cm | min. 100 N/cm |
| - dielectric constant | 1,2 | 1,2 |
| - dielectric strength | > 1,2 kV/layer | > 1 kV/layer |

4.3. Insulation - cross-linked low smoke halogen free polymer

- tensile strength 11,5 N/mm²
- elongation at break 280%
- hardness 45°Sh D
- oxygen index 33%

4.4. Filling sheath - a thermoplastic halogen free compound with oxygen index 40%**4.5. Concentric conductor**

soft copper wires + counter helix made of copper tape thickness 0,1mm and wrapped with polyester foil

4.6. Sheath:

- tensile strength 12 MPa
- elongation at break 180%
- hardness 50°Sh D
- oxygen index 40%



DRAWINGS

Nr	Nr Fires	Czas	Symbol kaba	Pozycja	Konstrukcja mocowania, odległość, obciążenie
1	46		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	1	Korytka kablowe KCP/KCOP 400H60/... B-400 1.2 m /10kg/m / grubość blachy 1,5 mm Mocowanie : Wspornik WPC/WPCO1000, Wysięgnik WMC/WMCO400 , pręt gwintowany PG M10 za pomocą uchwytu USV/USOV
2	45		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
3	67		HTKSH PH90 1x2x1,0		
4			HTKSH PH90 1x2x1,0		
5	66		HTKSHekw PH90 1x2x1,0		
6			HTKSHekw PH90 1x2x1,0		
7	44		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
8	43		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
9	42		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	2	Drabina kablowa DGP/DGOP400H60/... B-400 1.2 m /20kg/m / grubość blachy 1,5 mm Mocowanie : Wspornik WPC/WPCO1000, Wysięgnik WMC/WMCO400 , pręt gwintowany PG M10 za pomocą uchwytu USV/USOV
10	41		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
11	65		HTKSH PH90 1x2x1,0		
12			HTKSH PH90 1x2x1,0		
13	64		HTKSHekw PH90 1x2x1,0		
14			HTKSHekw PH90 1x2x1,0		
15	40		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
16	39		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
17	36		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	3	Korytka siatkowe KDS/ KDSO 400H60/... B-400 1.5 m /20kg/m / grubość drutu fi 4,5 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
18	35		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
19	34		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
20	33		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
21	62		HTKSH PH90 1x2x1,0		
22			HTKSH PH90 1x2x1,0		
23	32		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
24	31		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
25	30		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM	4	Korytka siatkowe KDS/ KDSO 400H60/... B-400 1.5 m /20kg/m / grubość drutu fi 4,5 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
26	29		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM		
27	28		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
28	27		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
29	61		HTKSHekw PH90 1x2x1,0		
30			HTKSHekw PH90 1x2x1,0		
31	22		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM	5	Korytka kablowe KGJ/KGOJ 400H60/... B-400 1.5 m /20kg/m / grubość blachy 0,9 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
32	21		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM		
33	20		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
34	19		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
35	57		HTKSHekw PH90 1x2x1,0		
36			HTKSHekw PH90 1x2x1,0		
37	18		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM	6	Korytka kablowe KGL/KGOL 300H60/... B-300 1.5 m /20kg/m / grubość blachy 0,7 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
38	17		NHXXCH FE180 PH90/E90 0,6/1kV 4x50/25RM		
39	16		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
40	15		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
41	56		HTKSHekw PH90 1x2x1,0		
42			HTKSHekw PH90 1x2x1,0		



DRAWINGS

Nr	Nr Fires	Czas	Symbol kaba	Pozycja	Konstrukcja mocowania, odległość, obciążenie
43	12		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	7	Korytka kablowe KGJ/KGOJ 400H60/... B-400 1.5 m /20kg/m / grubość blachy 0,9 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
44	11		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
45	10		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
46	9		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
47	55		HTKSH PH90 1x2x1,0		
48			HTKSH PH90 1x2x1,0		
49	8		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	8	Korytka kablowe KGL/KGOL 300H60/... B-300 1.5 m /20kg/m / grubość blachy 0,7 mm Mocowanie : Ceownik CWP/CWOP40H40/05, pręt gwintowany PG M10
50	7		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
51	6		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
52	5		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
53	54		HTKSH PH90 1x2x1,0		
54			HTKSH PH90 1x2x1,0		
55	47		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	9	Uchwyt kablowy UDF. Mocowanie do płyty gips karton co 600mm za pomocą kołka MOLLY 5x52/58
56			NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
57	48		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
58			NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
59	49		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
60			NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
61	68		HTKSHeqw PH90 1x2x1,0		
62			HTKSHeqw PH90 1x2x1,0		
63	69		HTKSH PH90 1x2x1,0		
64			HTKSH PH90 1x2x1,0		
65	38		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE	10	Obejma kablowa KSA Mocowanie co 600mm + puszki PMO1 i PMO2
66	63		HTKSH PH90 1x2x1,0		
67	37		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
68	26		NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE	11	Korytka siatkowe KDS/KDSO 60H60/... B-60 1.5 m /1,5kg/m / grubość drutu fi 4,5 mm Mocowanie : wieszak WKS/WKSO 60, pręt gwintowany PG M6
69			NHXXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE		
70	25		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
71			NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE		
72	60		HTKSHeqw PH90 1x2x1,0		
73			HTKSHeqw PH90 1x2x1,0		
74	59		HTKSH PH90 1x2x1,0		
75			HTKSH PH90 1x2x1,0		
76	24		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	12	Uchwyty kablowe UK1/UKO1+ SDP/SDOP 700. Mocowanie co 600mm
77			NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
78	23		NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
79			NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE		
80	58		HTKSH PH90 1x2x1,0		
81			HTKSH PH90 1x2x1,0		




DRAWINGS

Nr	Nr Fires	Czas	Symbol kaba	Pozycja	Konstrukcja mocowania, odległość, obciążenie
82	14		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	13	Obejma kablowa KSA Mocowanie co 600mm
83			NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
84	13	test	NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
85		test	NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
86	53		HTKSH PH90 1x2x1,0	14	Uchwyt kablowy UDF. Mocowanie do Ytongu co 600mm za pomocą kołka xxxx 6x30
87			HTKSH PH90 1x2x1,0		
88	52		HTKSHekw PH90 1x2x1,0		
89			HTKSHekw PH90 1x2x1,0		
90	4		NHXXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		
91			NHXXH FE180 PH90/E90 0,6/1kV 4x1,5 RE		
92	3		NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		
93			NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5 RE		
94	2		NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
95			NHXXH FE180 PH90/E90 0,6/1kV 4x50RM		
96	1		NHXCH FE180 PH90/E90 0,6/1kV 4x50/25RM		
97			NHXCH FE180 PH90/E90 0,6/1kV 4x50/25RM		

Zestawienie kabli Madex:


Lp.	Symbol kabla	Ilość [szt.]	Średnica [mm]	Ciężar kabla [kg/m]
1	HTKSH PH90 1x2x1,0	19	5,5	0,046
2	HTKSHekw PH90 1x2x1,0	16	6,7	0,05
3	NHXXH FE180 PH90/E90 0,6/1kV 4x1,5RE	14	15,4	0,34
4	NHXXH FE180 PH90/E90 0,6/1kV 4x50RM	18	33	2,56
5	NHXCH FE180 PH90/E90 0,6/1kV 4x1,5/1,5RE	12	17,3	0,39
6	NHXCH FE180 PH90/E90 0,6/1kV 4x50/25RM	8	37,5	2,92
	NHXXH-J FE180 PH90/E90 0,6/1kV 5x16 RE	10	27,7	1,39





DRAWINGS


A-A





DRAWINGS




B-B






DRAWINGS


C-C






DRAWINGS







E-E






DRAWINGS








DRAWINGS



14	Zacisk mocujący	ZMO	2
13	Śruba z łbem grzybkowym	SGNM6x12	8
12	Śruba z łbem grzybkowym	SGNM8x14	6
11	Śruba	SMM10x30	4
10	Podkładka	PP10	6
9	Nakrętka	NSM10	6
8	Śruba tulejowa rozporowa	PSROM10x80	3
7	Uchwyt	UPWO	2
6	Uchwyt sufitowy	USV/USOV	1
5	Pręt gwintowany	PGM10/...	1
4	Drabinka	DGOP600H60/3N	1
3	Korytko	KCP/KCOP400H60/3N	1
2	Wysięgnik	WMC/WMCO400	2
1	Wspornik sufitowy	WPCW/WPCO1000	1
L.p.	Nazwa	Symbol	Szt.




DRAWINGS



8	Podkładka	PP10	8
7	Nakrętka	NSM10	8
6	Zacisk śrubowy	ZS/ZSO	4
5	Uchwyt śrubowy	USSN/USSO	10
4	Korytka siatkowe	KDS/KDSO400H60/3	2
3	Tuleja rozporowa stalowa	TRSOM10	2
2	Pręt gwintowany	PGM10/...	2
1	Ceownik wzmacniony	CWP/CWOP40H40/05	2
L.p.	Nazwa	Symbol	Szt.




DRAWINGS



8	Podkładka	PP10	8
7	Nakrętka	NSM10	8
6	Śruba z łbem grzybkowym	SGNM6x12	15
5	Korytko	KGL/KGOL300H60/3	1
4	Korytko	KGJ/KGOJ400H60/3	1
3	Tuleja rozporowa stalowa	TRSOM10	2
2	Pręt gwintowany	PGM10/...	2
1	Ceownik wzmocniony	CWP/CWOP40H40/05	2
L.p.	Nazwa	Symbol	Szt.



DRAWINGS



7	Korytko siatkowe	KDS/KDSO60H60/3	1
6	Uchwyt śrubowy	USSN/USSO	2
5	Wieszak	WKS/WKSO60	1
4	Nakrętka	NSM6	2
3	Podkładka	PP6	2
2	Pręt gwintowany	PGM6/...	1
1	Tuleja rozporowa stalowa	TRSOM6	1
L.p.	Nazwa	Symbol	Szt.

3	Śruba	SGN M8x14		8	
2	Łącznik	LDCH60N		2	
1	Drabinka	DGP600H60/3N		2	
Pos.	Benennung	Zeichnung-Nr	Material	Stck.	Katalogs Nr.
	Odchyłka wymiarów nietolerowanych		Gatunek		Masa [kg]
			Nr normy		Podziałka
			polfabrykat (nr normy)		Format A4
					Arkusze 1
					Arkusze 1
Projektował				Nazwa rysunku	
Rysował				DGP600H60/3N	
Sprawdził					
Zatwierdził				Nr programu maszynowego	Nr zmiany
				Nr rysunku	
	Profesjonalne Systemy Tras Kablowych				



DRAWINGS

Technical drawing of cable tray assembly showing side view, top view, and detail views of components 1, 2, 3, and 4.

Poz.1		Poz.4
A	Typ	Typ
100	KCP/KCOP100H60/3N-F	BL/BLQ100N
200	KCP/KCOP200H60/3N-F	BL/BLQ200N
300	KCP/KCOP300H60/3N-F	BL/BLQ300N
400	KCP/KCOP400H60/3N-F	BL/BLQ400N

4	Blacha łącznikowa	BL/BLQ400N		1	
3	Śruba z łbem grzybkowym	SGN M6x12		24	
2	Łącznik	LPP/LPPH60N		2	
1	Koryto	KCP/KCOP400H60/3N		2	
L.p.	Nazwa	Symbol	Materiał	Szt.	Nr katalogowy
			Gatunek	Masa [kg]	Podziałka
			Nr normy		7:50
			polifabrykat (nr normy)		Arkusz 1
					Arkuszy 1
Projektował			Nazwa rysunku	Połączenie KCP/KCOP400H60/3N	
Rysował	J.Grochowski	Podpis			
Sprawdził					
Zatwierdził					
			Profesjonalne Systemy Tras Kablowych		
			Nr programu maszynowego	Nr znlany	
			Nr rysunku		



DRAWINGS

1



2

2	USSN/USSD N	5
1	KDS/KDS□400H60/3	2
L.p.	Symbol	Ilość szt.
	Wykresy wykresów elektrycznych	
Projektował		
Rysował		
Sprawdził		
Zatwierdził		
Profesjonalne Systemy Tras Kablowych		
Nazwa rysunku		
Data		
Materiał		
Nazwa rysunku		
Masa (kg)		
Podziałka		
Format A3		
Arkusz 1		
Arkusz 1		
Połączenie KDS/KDS□400H60/3		
Nr programu rysunkowego		
Nr rysunku		
Nr zmiany		



DRAWINGS

Poz.1		Poz.2
A	Typ	Ilość
100	KGJ/KGDJ100H60/3	6
200	KGJ/KGDJ200H60/3	7
300	KGJ/KGDJ300H60/3	8
400	KGJ/KGDJ400H60/3	10




2	Śruba z łbem grzybkowym	SGN M6x12		10	
1	Korytka	KGJ/KGDJ400H60/3		2	
L.p.	Nazwa	Symbol	Material	Szt.	Nr katalogowy
	Długość wytworów niezłazowanych		Gatunek Nr normy polifabrykat (nr normy)	Masa (kg)	Podziałka
Projektował			Nazwa rysunku		Format A4
Rysował					Arkusz 1
Sprawił					Arkuszy 1
Zatwierdził					
 Profesjonalne Systemy Tras Kablowych				Nr programu Nr rysunku	
				Nr zbilans	



DRAWINGS

Poz.1		Poz.2
A	Typ	Ilość
100	KGL/KGDL100H60/3	6
200	KGL/KGDL200H60/3	7
300	KGL/KGDL300H60/3	8





2	Śruba z łbem grzybkowym	SGN M6x12		8	
1	Korytka	KGL/KGDL300H60/3		2	
L.p.	Nazwa	Symbol	Materiał	Szt.	Nr katalogowy
	Długość wyłazła niezłazowana		Głębokość Nr normy półfabrykat (nr normy)	Masa B.gł	Podziałka
Projektował					Format A4
Rysował					Arkusz 1
Sprawił					Arkuszy 1
Zatwierdził					
Profesjonalne Systemy Tras Kablowych				Potężenie KGL/KGDL300H60/3	
				Nr programu maszynowego Nr rysunku	
				Nr zmiany	






DRAWINGS




Symbol	Szerokość A(mm)	Długość L(mm)
KCP/KCOP100H60/3N	100	3000
KCP/KCOP200H60/3N	200	3000
KCP/KCOP300H60/3N	300	3000
KCP/KCOP400H60/3N	400	3000



	Odchyłka wyrównoważ metalowych		Materiał	Gatunek		Masa [kg]	Podziałka 1:5	Format A4
				Nr normy				Arkusz
Projektował	Nazwisko	Podpis	Data	półfabrykat (nr normy)				
Rysował				Nazwa rysunku				
Sprawdził				KCP/KCOP...H60/3N				
Zatwierdził				Nr programu maszynowego				
			Nr rysunku					Nr zmiany




Typ	Szerokość A(mm)	Długość L(mm)
KGJ/KGQJ100H60/3	100	3000
KGJ/KGQJ200H60/3	200	3000
KGJ/KGQJ300H60/3	300	3000
KGJ/KGQJ400H60/3	400	3000



	Odczytyka wyłaróu nietolerowanych		Materiał		Gatunek	Masa lkgj	Podziałka	Format
					Nr normy		1:5	A4
					pólfabrykat (nr normy)			Arkuszy
								Arkuszy
Projektował	Nazwisko		Podpis	Data	Nazwa rysunku			
Rysował					KGJ/KGJ...H60/3			
Sprawił								
Zatwierdził								
					Nr programu maszynowego			Nr ziny
 Profesjonalne Systemy Tras Kablowych					Nr rysunku			

	Odczytyka wymiarów nieolerowanych		Materiał	Gatunek		Masa kglj	Podziałka	Format
				Nr normy			1:5	A4
				półfabrykat (nr normy)				Arkusz
								Arkuszy
Projektował				Nazwa rysunku				
Rysował				KGL/KGOL...H60/3				
Sprawił								
Zatwierdził				Nr programu maszynowego				Nr zbilony
				Nr rysunku				
Profesjonalne Systemy Trasy Kablowych								

DRAWINGS




		Odczytka wymiarów nieolerowanych		Materiał		Masa [kg]		Podziałka		Format A4	
				Gatunek						Arkusze	
				Nr normy						Arkuszy	
				półfabrykat (nr normy)							
Projektował		J.GROCHOWSKI		Data		20.10.05		Nazwa rysunku <i>LDC/L DOCH60N</i>			
Rysował		J.Grochowski				20.10.05					
Sprawdził		T.WŁODARCZYK				20.10.05					
Zatwierdził		JKLICZEK				20.10.05					
						Nr programu				Nr zmiany	
						Naszywanego					

Profesjonalne Systemy Tras Kablowych




Profesjonalne Systemy Tras Kablowych


DRAWINGS



	Długość wymiarów nieolerowanych		Materiał	Gatunek	Masa [kg]	Podziałka	Format A4
				Nr normy			
				półfabrykat (nr normy)			
						2:1	Arkusz
							Arkuszy
Projektował	J.GRUCHOWSKI		Podpis	Data	Nazwa rysunku		
Rysował	J.Grachowski				LPP/LPPH60N		
Sprawdził	T.WŁODARCZYK						
Zatwierdził	JKLICZEK						
					Nr programu maszynowego		Nr zmiany
					Nr rysunku		

20	Uchwyt kabla	UDF 43	405543	21,5	60,0	20,0	2,0
19	Uchwyt kabla	UDF 40	405540	20,0	57,0	20,0	2,0
18	Uchwyt kabla	UDF 37	405537	18,5	54,0	20,0	2,0
17	Uchwyt kabla	UDF 34	405534	17,0	51,0	20,0	2,0
16	Uchwyt kabla	UDF 31	405531	15,5	48,0	20,0	2,0
15	Uchwyt kabla	UDF 28	405528	14,0	45,0	20,0	2,0
14	Uchwyt kabla	UDF 25	405525	12,5	44,0	20,0	2,0
13	Uchwyt kabla	UDF 22	405522	11,0	41,0	14,0	2,0
12	Uchwyt kabla	UDF 20	405520	10,0	39,0	14,0	2,0
11	Uchwyt kabla	UDF 18	405518	9,0	37,0	14,0	2,0
10	Uchwyt kabla	UDF 16	405516	8,0	35,0	14,0	2,0
9	Uchwyt kabla	UDF 15	405515	7,5	34,0	14,0	2,0
8	Uchwyt kabla	UDF 14	405514	7,0	33,0	14,0	1,2
7	Uchwyt kabla	UDF 12	405512	6,0	30,0	14,0	1,2
6	Uchwyt kabla	UDF 10	405510	5,0	28,0	14,0	1,2
5	Uchwyt kabla	UDF 9	405509	4,5	27,0	14,0	1,2
4	Uchwyt kabla	UDF 8	405508	4,0	26,0	14,0	1,2
3	Uchwyt kabla	UDF 7	405507	3,5	25,0	14,0	1,2
2	Uchwyt kabla	UDF 6	405506	3,0	24,0	14,0	1,2
1	Uchwyt kabla	UDF 5	405505	2,5	23,0	14,0	1,2
LP	Nazwa wyrobu	Symbol	Nr Katalogowy	R [mm]	L [mm]	H [mm]	G [mm]

	Odchyłka wymiarowa nieolerowanych		$\pm 0,5$	Materiał Gatunek Nr normy półfabrykat (nr normy)	PN-EN 10327:2005 -----	Masa [kg] ---	Podziałka 1:1	Format A4 Arkusz --- Arkuszy ---	
	Projektował Rysował Sprawdził Zatwierdził	Jacek Grochowski Jakub Rudak Jacek Kliczek Jacek Kliczek	Podpis _____ _____ _____ _____	Data 20.10.05 20.02.08 20.02.08 20.02.08	Nazwa rysunku UDF 5-43				Nr zmiany _____ _____ _____
	 Profesjonalne Systemy Tras Kablowych				Nr rysunku 4055.....				




UK/UK01/64-70	72	116	70
UK/UK01/58-64	66	103	64
UK/UK01/46-52	54	97	52
UK/UK01/40-46	48	86	46
UK/UK01/34-40	42	78	40
UK/UK01/28-34	36	71	34
UK/UK01/22-28	30	61	28
UK/UK01/16-22	24	57	22
SYMBOL	A[mm]	H[mm]	D[mm]


	Długość (wymiarów) nietolerowanych		Materiał	Gatunek	Masa [kg]	Podziałka	Format
				Nr normy			
				półfabrykat (nr normy)		1:1	Arkusz 1
Projektował	Nazwisko	Podpis	Data	Nazwa rysunku			
Rysował				UK/UK01/... - ...			
Sprawdził							
Zatwierdził							
				Nr programu maszynowego	---	Nr zbilansy	
			Profesjonalne Systemy Tras Kablowych				

L.p.	Symbol	b	H	Śruba
1.	UKZ/UKZ01/16-22	22mm	61,5mm	M8x40
2.	UKZ/UKZ01/22-28	28mm	68mm	M8x40
3.	UKZ/UKZ01/28-34	34mm	76mm	M8x40
4.	UKZ/UKZ01/34-40	40mm	84,5mm	M8x40
5.	UKZ/UKZ01/40-46	46mm	91,5mm	M8x50
6.	UKZ/UKZ01/46-52	52mm	102mm	M8x50
7.	UKZ/UKZ01/58-64	64mm	111mm	M8x50


	Długość wymiary niez tolerowane			Materiał	Gatunek	Masa [kg]	Podziałka	Format
					Nr normy			
					półfabrykat (nr normy)	-----		Arkuszy
Projektował					Nazwa rysunku			
Rysował					UKZ/UKZ01/...			
Sprawdził								
Zatwierdził								
				Nr programu maszynowego		Nr zmiany		
				Nr rysunku				
				Profesjonalne Systemy Tras Kablowych				

DRAWINGS






	Długość wymiarów niezależnych		Materiał		Gatunek		Masa [kg]	Podziałka	Format
					Nr normy		-----	2:1	Arkusz 1
Projektował		Nazwisko		Podpis		Data		Nazwa rysunku	
Rysował		M. Sobolewski						USSN/USS□	
Sprawdził		J. Kłiczek						Nr programu maszynowego	
Zatwierdził		J. Kłiczek						Nr rysunku	
		Profesjonalne Systemy Tras Kablowych						Nr zmiany	

Page: 60/64




DRAWINGS



L	Typ
200	WPCW/WPCD200N
300	WPCW/WPCD300N
400	WPCW/WPCD400N
500	WPCW/WPCD500N
600	WPCW/WPCD600N
700	WPCW/WPCD700N
800	WPCW/WPCD800N
900	WPCW/WPCD900N
1000	WPCW/WPCD1000N

	Długość wymiary niezależnych	Materiał	Gatunek	Masa [kg]	Podziałka	Format A4
			Nr normy		1:1	Arkusz 1
			półfabrykat (nr normy)			Arkuszy 1
Projektował	Nazwisko Podpis	Data	Nazwa rysunku WPCW/WPCD...N			
Rysował						
Sprawił						
Zatwierdził						
 Profesjonalne Systemy Tras Kablowych		Nr programu maszynowego		Nr złącz		
		Nr rysunku				



System E-30, E-90 - Puszki łączeniowo-rozgałęźne



Puszka łączeniowo-rozgałęźna




PMO1 (5/6)



PMO1 (5/3)



PMO1 (3/3)



PMO1

SYMBOL	nr katalogowy	szk.
PMO1(5/6)	801100	1
PMO1(5/3)	801200	1
PMO1(3/3)	801300	1

PMO1 E

PMO1(5/6) E	801101	1
PMO1(5/3) E	801201	1
PMO1(3/3) E	801301	1

INFORMACJA TECHNICZNA

Stosowana jako puszka:

- przelotowa o przekroju kabla od 0,5 mm² do 6 mm²,
- rozgałęźna o przekroju kabla od 0,5 mm² do 1,5 mm².


Puszka wykonywana jest w wersji:

- PMO1 5/6 - 5 kostek zaciskowych, 6 dławików gumowych
- PMO1 5/3 - 5 kostek zaciskowych, 3 dławiki gumowe
- PMO1 3/3 - 3 kostki zaciskowe, 3 dławiki gumowe
- PMO1 5/6 E - 5 kostek zaciskowych, 6 dławików gumowych
- PMO1 5/3 E - 5 kostek zaciskowych, 3 dławiki gumowe
- PMO1 3/3 E - 3 kostki zaciskowe, 3 dławiki gumowe


Maksymalne przekroje żył i ich ilość mieszcząca się w gnieździe kostki:

5 x 0,5 mm ²	1 x 2,5 mm ²
5 x 0,75 mm ²	1 x 4 mm ²
4 x 1 mm ²	1 x 6 mm ²
3 x 1,5 mm ²	

PMO1 (5/6)





PMO1 (5/3) | PMO1 (3/3)



ZASTOSOWANIE

Puszka łączeniowa i rozgałęźna, U_i=400 V, z trwałym zachowaniem funkcji łączenia E30 / E60 / E90 wg DIN 4102 część 12. Stopień ochrony IP54, zakres uszczelnienia od 7 mm do 18,5 mm. Mocowanie poprzez zewnętrzne uchwytty montażowe: do betonu za pomocą kołków stalowych SR0M6x30, do drabinek i korytek kablowych za pomocą śruby SGK6x12.

Puszka łączeniowo-rozgałęźna



PMO2 (5/6)



PMO2 (5/3)



PMO2 (3/3)



PMO2

SYMBOL	nr katalogowy	szk.
PMO2(5/6)	802010	1
PMO2(5/3)	802020	1
PMO2(3/3)	802030	1

PMO2 E

PMO2(5/6) E	802011	1
PMO2(5/3) E	802021	1
PMO2(3/3) E	802031	1

INFORMACJA TECHNICZNA

Stosowana jako puszka:

- przelotowa o przekroju kabla od 1,0 mm² do 10 mm²,
- rozgałęźna o przekroju kabla od 1,0 mm² do 4 mm².


Puszka wykonywana jest w wersji:

- PMO2 5/6 - 5 kostek zaciskowych, 6 dławików gumowych
- PMO2 5/3 - 5 kostek zaciskowych, 3 dławiki gumowe
- PMO2 3/3 - 3 kostki zaciskowe, 3 dławiki gumowe
- PMO2 5/6 E - 5 kostek zaciskowych, 6 dławików gumowych
- PMO2 5/3 E - 5 kostek zaciskowych, 3 dławiki gumowe
- PMO2 3/3 E - 3 kostki zaciskowe, 3 dławiki gumowe


Maksymalne przekroje żył i ich ilość mieszcząca się w gnieździe kostki:

6 x 1 mm ²	2 x 4 mm ²
6 x 1,5 mm ²	1 x 6 mm ²
4 x 2,5 mm ²	1 x 10 mm ²

PMO2 (5/6)



PMO2 (5/3) | PMO2 (3/3)



ZASTOSOWANIE

Puszka łączeniowa i rozgałęźna, U_i=400 V, z trwałym zachowaniem funkcji łączenia E30 / E60 / E90 wg DIN 4102 część 12. Stopień ochrony IP54, zakres uszczelnienia od 11 mm do 24 mm. Mocowanie poprzez zewnętrzne uchwytty montażowe: do betonu za pomocą kołków stalowych SR0M6x30, do drabinek i korytek kablowych za pomocą śruby SGK6x12.

MATERIAŁ

PMO1, PMO2, - blacha stalowa, malowana proszkowo RAL 2003
PMO1 E, PMO2 E, - blacha kwasoodporna, 1.4301 malowana proszkowo RAL 2003
Kostka zaciskowa wykonana jest ze specjalnej ceramiki odpornej na wysokie temperatury, dławik wykonany jest z tworzywa bezhalogenowego mocowanie poprzez zewnętrzne uchwytty montażowe



7. FINAL PROVISION

- § This report details the method of construction, the test conditions and results obtained when the specific element of construction described herein was following the procedure outlined in STN EN 1363-1, and where appropriate STN 92 0205:2012. Any significant deviation with respect to size, constructional details, loads, stresses, edge or end conditions other than those allowed under the field of direct application in the relevant test method is not covered by this report.
- § Because of the nature of the fire resistance testing and consequent difficulty in quantifying the uncertainty of measurement of fire resistance, it is not possible to provide a stated degree of accuracy of the result.
- § The test results refer only to the tested subjects. This test report is not an approval of the tested product by the test laboratory or the accreditation body overseeing the laboratory's activities. The test was carried out on testing equipment that is the property of FIRES, s.r.o., Batizovce. Without the written permission of the test laboratory this test report may be copied and/or distributed only as the whole. Any modifications of the test report can be made only by the fire resistance test laboratory FIRES, s.r.o., Batizovce.

Approved by:

Prepared by:

Ing. Štefan Rástocký
leader of the testing laboratory



Bc. Dávid Šubert
technician of the testing laboratory

8. NORMATIVE REFERENCES

STN EN 1363-1: 2001	Fire resistance tests. Part 1: General requirements
STN 92 0205:2012	Fire behaviour of construction products and building constructions. Circuit integrity maintenance of cable systems. Requirements, testing and classification.
DIN 4102 – 2:1977-09	Fire behaviour of building materials and elements - requirements and testing
DIN 4102 – 12:1998-11	Fire resistance of electric cable systems required to maintain circuit integrity
ZP-27/2008 PAVUS	Test method for determination of functionality class of cables and cable loadbearing constructions - cable circuits in case of fire

THE END OF THE TEST REPORT